BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2011-12/FP/WORK_INDENT2960/CALL-3

APPROVED SCHEDULE - B

T.ND No. No.EE/BTP/BBMP/E-PMT/12/2012-13, Date: 14.12.2012

Name of the work:- Providing RCC drain in Main roads and cross roads of KalappaLayout in ward no [redacted].

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of GOPIREDDY	
				In Figures	In Words
1	805.2	Removing B.S. slab of Drain and stacking. (P No.24 / i 5.32 SR 2010-11)	Cum	42.68	Rupees Forty Two and Sixty Eight Paise Only
2	724.68	KSRRB 300-1 : Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2m meters and an average lift upto 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications complete as per specifications. (P No.126 / i 19.1 SR 2010-11)	Cum	129.34	Rupees One Hundred Twenty Nine and Thirty Four Paise Only
3	120.78	KSRB 4-1.3: Providing and laying in position plain cement concrete mix 1:4:8 using 40mm and down size graded granite metal machine, concrete laid in layers not exceeding 15 cms. Thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specification No.KBS 4.1, 4.2 (P No. 12 / i 4.3 SR 2010-11)	Cum ~~Sqm~~	3488.97	Rupees Three Thousand Four Hundred Eighty Eight and Ninety Seven Paise Only
4	2717.58	KSRB 4-6.4: Providing and removing centering,shuttering, strutting, propping etc.., and removal of form work for vertical surface such as walls at any thickness,including attached pilasters, buttresses,plinth and string courses cost of all materials,labour complete as per specifications. (P No. 14 / i 4.31 SR 2010-11)	Cum	172.45	Rupees One Hundred Seventy Two and Forty Five Paise Only
5	241.56	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of mix 1:1.5:3 with 20mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slab, staircase, lintels, retaining walls, walls (any thickness) includingattached pilasters, columns,piers, abutments, pillars,posts,struts, buttresses, string or lacing courses,parapets,coping, bed blocks, anchor blocks plain window cills,fillets etc.., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Specification No. KBS 4.1, 4.6 (P No. 12 / i 4.11 SR 2010-11)	Qtl	5237.22	Rupees Five Thousand Two Hundred Thirty Seven and Twenty Two Paise Only
6	362.34	KSRB 2.3 : Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20cms.in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5m including cost of alllabour complete asperspecifications. (P No. 6 Item No.2.10 PWD SR 2010-11)	Cum	87.09	Rupees Eighty Seven and Nine Paise Only
7	181.17	KSRB 4.9.2 : Providing T.M.T steel reinforcement for RCC work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and westage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. (P No. 16 Item No.4.46 PWD SR 2010-11)	Sqm	5826.80	Rupees Five Thousand Eight Hundred Twenty Six and Eighty Paise Only

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of GOPIREDDY	
				In Figures	In Words
8	805.2	Refixing stone slabs of drains and pointing in C.M. (1:3) (P No.24 / i 5.33 SR 2010-11)	Sqm	56.89	Rupees Fifty Six and Eighty Nine Paise Only
9	579.79	Leadfor disposalof debris shall be payable at the following rates	Cum	79.98	Rupees Seventy Nine and Ninety Eight Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92